

12-Dec-24

POLY_ID	PROJ_DESC
712930	25ASS-CLAIRMONT ST-BISCAYNE TO ADMIRALTY
714770	25ASS-HOWARD ST-WESTWOOD N TO CUL-DE-SAC
720270	25ASS-MONROE AVE-20TH TO 19TH
711960	28ASS-BELMONT AVE-EISENHOWER TO SPRING
716650	28ASS-OLIVE ST-ILLINOIS TO OREGON
105030	29ASS-DEKOVEN AVE-HOLBORN TO CLARK
703890	29ASS-ELISA DR-DEAD END TO OSTERGAARD
715060	29ASS-JONATHON DR-CUL-DE-SAC TO MAIN
715310	29ASS-KENTUCKY ST-TAYLOR AVE TO CUL-DE-SAC
712040	BISCAYNE AVE-PRINCESS PL TO DUCHESS DR
716660	OLIVE ST-INDIANA TO KENTUCKY
718470	ST. CLAIR ST-LOMBARD TO WILLMOR

Assessable Pavements under 40 PCI

PAVT_POLYGON_NAME	LAST_DENIED	MUST_FIX_YEAR
CLAIRMONT ST - BISCAYNE AVE TO ADMIRALTY AVE - ENTIRE BLOCK		2025
HOWARD ST - WESTWOOD DR TO CUL-DE-SAC - ENTIRE BLOCK	6/4/2019	2025
MONROE AVE - TWENTIETH ST TO NINETEENTH ST - ENTIRE BLOCK	6/4/2019	2025
BELMONT AVE - EISENHOWER DR TO SPRING ST - ENTIRE BLOCK	5/17/2022	2028
OLIVE ST - ILLINOIS ST TO OREGON ST - ENTIRE BLOCK	5/17/2022	2028
DEKOVEN AVE - HOLBORN ST TO CLARK ST - ENTIRE BLOCK	5/16/2023	2029
ELISA DR - CITY LIMITS TO OSTERGAARD AVE - ENTIRE BLOCK	5/16/2023	2029
JONATHON DR - CUL-DE-SAC TO NORTH MAIN ST - ENTIRE BLOCK	5/16/2023	2029
KENTUCKY ST - TAYLOR AVE TO CUL-DE-SAC - ENTIRE BLOCK	5/16/2023	2029
BISCAYNE AVE - PRINCESS PL TO DUCHESS DR - ENTIRE BLOCK		
OLIVE ST - INDIANA ST TO KENTUCKY ST - ENTIRE BLOCK		
ST. CLAIR ST - LOMBARD AVE TO WILLMOR ST - ENTIRE BLOCK		

Green = 2025 construction from 2024 hearing results

Blue = Proposed for 2025 hearing and 2026 construction

Red = Not previously planned for hearing based on PCI but now should be considered for 2025 hearing and 20:

Must_Strat	PCI_Value	PCI_DATE	YR_CONST	PVMT_DESC_BRF
7" CONCRETE STD RECONSTRUCT	21	5/16/2023	2005	ASPH-LOC
7" CONCRETE STD RECONSTRUCT	24	5/16/2018	1974	BIT-LOC
7" CONCRETE STD RECONSTRUCT	22	5/9/2016	1971	BIT-LOC
7" CONCRETE STD RECONSTRUCT	14	11/8/2022	1975	BIT-LOC
7" CONCRETE STD RECONSTRUCT	39	4/7/2020	1977	BIT-LOC
9" CONCRETE RECONSTRUCT	23	8/29/2024	1991	AS/BIT>LOC
7" CONCRETE STD RECONSTRUCT	16	7/30/2024	1971	BIT-LOC
7" CONCRETE STD RECONSTRUCT	16	7/25/2024	1967	OIL-LOC
7" CONCRETE STD RECONSTRUCT	18	4/13/2023	1973	BIT-LOC
	27	5/16/2023	2007	ASPH-LOC
	35	7/8/2024	1977	BIT-LOC
	25	7/22/2024	1972	BIT-LOC

26 construction