

526 Marquette Street
Racine, WI
Additional Below Grade Removal
As of 10-10-2018

	Notes	length	Height	Width	Qty	CY
STRUCTURE A	Walls	60	4	0.58	3	15
	Pad	10	10	2	1	7
	Slab	60	27	0.67	1	40
STRUCCTURE B	Walls	108	8	1	1	32
	Slab	45	9	0.67	1	10
STRUCTURE C	Slab	186	92	1.08	1	684
STUCTIONE D	Walls	58	8	1	1	17
	Slab	20	18	0.67	1	9
STRUCTURE E	Walls	55	8	1	1	16
	Slab	20	15	0.67	1	7
STRUCTURE F	wall only	10	8	1	1	3
STRUCTURE G	Walls	49	8	1	1	15
	Slab	17	15	0.67	1	6
STRUCTURE H	Pad	12	12	3	1	16
STRUCTURE I	Pad	14	14	6	1	44
total						923
						Cubic Yards

Item	hours	cost	total
330 Backhoe	138	\$ 249.00	\$ 34,362.00
Attachment	70	\$ 145.00	\$ 10,150.00
Laborer	70	\$ 89.00	\$ 6,230.00
Supervisor	35	\$ 130.00	\$ 4,550.00
Demolition Total:			\$ 55,292.00
Unit Price to stockpile and crush	923	\$ 15.00	\$ 13,845.00
Grand Total:			\$ 69,137.00

Unit Price for future removals \$ 74.90 per cubic yard